

**LOCAL DEVELOPMENT PLAN APPROVAL EXPIRED**

This Local Development Plan expired on 19 October 2025, pursuant to Clause 57 of the Planning and Development (Local Planning Schemes) Regulations 2015, being 10 years after the Regulations came into effect.

2.5m minimum front setback



1.8m minimum second storey setback

1m minimum secondary street setback

Nil side setback for garages/carpports

1.0m minimum laneway setback with no protrusion of eaves into the setback

2.5m minimum Public Open Space setback



(A) Typical Enlargement



Location Plan

This Detailed Area Plan has been adopted by Council and signed by the Manager, Statutory Planning

*[Signature]*  
Manager, Statutory Planning

17/11/11  
Date


*[Signature]*  
C. REGUERO  
BUILDING SERVICES  
15.11.11

The City of Rockingham Town Planning Scheme No.2 and the Residential Design Codes are varied in the following manner:

- The Residential Design Code of R30 applies to all lots on this Detailed Area Plan (DAP).
- All dwellings and ancillary development must be located within the building envelopes as depicted on this DAP.
- The requirements of the Residential Design Codes and Town Planning Scheme shall be satisfied in all other matters.
- Consultation with adjoining or other landowners to achieve a variation to the Residential Design Codes, as provided for by this DAP, is not required.
- A five percent (5%) variation to minimum open space requirements (in addition to that described in the Open Space definition of the Codes) shall be permitted for single storey dwellings. Open Space shall be calculated in accordance with the provisions of the 2008 Residential Design Codes.
- Setback variations to corner lots may be approved at the discretion of the Manager, Building Services of the City of Rockingham where the configuration of these lots may limit compliance with setback requirements.
- Each dwelling is to have a double garage/carpport accessed from the rear laneway.
- No eaves shall protrude into the one (1) metre laneway setback.
- A nil setback is permissible on the lots where shown on the DAP. Side setbacks for the lots on this DAP may be reduced to nil for 2/3 the length of the Western boundary (behind the front setback line) provided that walls do not exceed 3m average and 3.5m maximum height.
- Eastern boundary setback as per Residential Design Codes.
- Garages/carpports may be setback a maximum of 6m from a rear laneway to provide for additional vehicular parking.
- Patios and verandahs and the like are permitted within the Public Open Space setback with a 1m minimum setback.
- 2.5m minimum Public Open Space setback to the dwelling. Sheds and garages are not permitted within the Public Open Space setback area.
- Dwellings must have at least one habitable room window facing the Public Open Space.



**DETAILED AREA PLAN**  
**- AVALON AT BALDIVIS**  
**LOTS 648-661**  
Plan 1 of 1



133 Scarborough Beach Road, Mount Hawthorn WA 6016  
PO Box 99, MOUNT HAWTHORN WA 6915  
T: 08 9443 1511 F: 08 9444 3901  
E: whelans@whelans.com.au W: www.whelans.com.au



s:\Projects\15\15172\Planning\Drafting & Design\design\111011  
DAP Lots 648-661 baldivis.dgn 15/11/11