

# R-CODE VARIATIONS

The provisions addressed below relate to Baldivis North Estate Lots 325 - 331 (Stage 5).

The Detailed Area Plan has been approved under Clause 4.23.1 (c) (i) of Town Planning Scheme No. 2. The requirements of the City of Rockingham Scheme and R-Codes shall be satisfied in all other matters.

## GENERAL PROVISIONS

R-Coding	R30	
Minimum Open Space	40% <i>(5% variation to R-Codes)</i>	
Building Setbacks	Minimum	Maximum
Primary Street	2.0m	4.0m
Side	<i>Refer provisions below *</i>	
North Boundary	As per R-Codes	-
South Boundary	Nil	-
Secondary Street	1.5m	-
Rear	As per R-Codes	-
Garages	4.5m	-

Setback variations to corner lots may be approved at the discretion of the Manager, Building Services where the configuration of these lots limits compliance with setback requirements.

All dwellings and ancillary development must be located within the building envelopes as depicted on the Detailed Area Plan.

### \*Side Setbacks:

- (i) A nil setback is permissible on the southern boundary of each lot. Nil setback wall heights shall not exceed 3.5m (max) and shall be no more than 2/3 the length of the boundary behind the prescribed primary street setback line of 4.0m.


### PRIMARY DWELLING ORIENTATION

Dwellings shall be designed to include at least one habitable room window facing the primary street.

### DESIGN FOR CLIMATE

All north facing walls containing window or door openings (excluding walls less than 0.9m from the boundary) shall incorporate eaves of a minimum 450mm overhang to provide passive shading during the summer.

## LOCATION PLAN



# DETAILED AREA PLAN

Lots 325 - 331 Huggins Way  
BALDIVIS

LOCAL DEVELOPMENT PLAN APPROVAL EXPIRED


This Local Development Plan expired on 19 October 2025, pursuant to Clause 57 of the Planning and Development (Local Planning Schemes) Regulations 2015, being 10 years after the Regulations came into effect.

### LEGEND:

- Building Envelope
- Recommended garage location
- Designated garage location

This Detailed Area Plan has been endorsed by Council under Clause 4.23.1(c) of Town Planning Scheme No.2.

Manager, Statutory Planning,  
City of Rockingham:   
Date: 15/10/12



COMPILED: DPS, MAPS	DRAWN BY: MDH
DATE: 10/09/2012	REVISED: 3/10/2012
GRID: MGA 50	DATUM: AHD
DRAWING NUMBER: ARBBD082d-DAP	JOB CODE: ARBBD082d-DAP
FILE ID: M:\ARBBD\BASE\ARBBD082d-DAP.dgn	

Copyright Development Planning Strategies. No part of this plan may be reproduced in any form without prior consent from DPS. All care has been taken in preparation of this plan but no responsibility is taken for any errors or omissions and is subject to change. Areas and dimensions shown on plan are subject to final survey. Carriageways depicted on plan are diagrammatic only.

Development Planning Strategies  
28 Brown St, East Perth WA 6004  
PO BOX 6697 EAST PERTH 6892  
T (08) 9268 7900  
F (08) 9268 7999  
E dps@dpswa.com.au