

DEVELOPMENT REQUIREMENTS

Town Planning Scheme No.2 and the Residential Design Codes are varied as follows:

1. *The R-Code is R30.*
2. *Bollards must be installed to prevent vehicle access between the driveway and the PAW. No fencing to the PAW is permitted, except for fencing to Lot 5 where the pre-existing dwelling is retained.*
3. *The major entry (front door) to dwellings on Lots 1-4 must be to the western side of the dwelling, and the major entry of the dwelling on Lot 6 to the eastern side of the dwelling.*
4. *Lots 7-12 must comply with table 3 of the Residential Design Codes for category A area buildings.*
5. *Development on Lots 1, 7 and 12 being designed to allow vehicles on these lots to enter the driveway in forward gear.*
6. *Site levels being generally consistent with adjoining properties.*
7. *Alternative garage locations to those shown on the Plan may be approved by the Manager, Building Services.*
8. *Outdoor living areas being located on the northern side of the dwelling, or in an alternative location subject to the design achieving solar orientation.*
9. *Front fencing to the western boundary of Lots 1, 2, 3, 4 and the future subdivision of Lot 5 being not higher than 0.75 m.*

LEGEND

- Indicative Garage Location
- Paved Area
- V.P. — Visitors Parking (6 parking bays)
- Subject Area

DETAILED AREA PLAN

LOT 96 & 97, BRIXHAM WAY
WARNBRO
CITY OF ROCKINGHAM

This Detailed Area Plan has been approved by the Manager, Statutory Planning

2/10/09

Manager, Statutory Planning — *Date*

MASTERPLAN
TOWN PLANNING CONSULTANTS
77 Thomas Street
Subiaco, W.A. 6008
ph: (08) 9388 3077 fax: (08) 9388 3088
email: reception@masterplan.com.au
A.B.N. 31 374 209 504

date: 03.03.08
scale @ A3: 1:500
ref: A245 DAP Rev A
17.09.09
revised: 24.09.09

apc Australian Association of Planning Consultants